
# Toth (molina) - [Tits] have yellowed by the property of the p

VOL. IV

AUGUST, 1923


NO. 6



REFRESHING SCENE ON YONAHLOSSEE ROAD—NEAR BLOWING ROCK

Report of Inspection of

# A PERMANENT CULVERT



An Armco Culvert in "The Land of the Sky."

Recently installed on the State Road over Grandfather Mountain, Second highest peak east of the Rockies. Located between Blowing Rock and Linville, North Carolina.

The culvert projects over the edge of the road about 14 feet, spilling the water far down the mountain side. This could not be done with any other kind of culvert pipe. Corrugated Culverts have the greatest strength and elasticity.



#### THE DIXIE CULVERT & METAL COMPANY

ATLANTA, GEORGIA

J. G. Baldwin, Asheville, N. C. W. H. McNeill, Lakeview, N. C.





# NORTH CAROLINA HIGHWAY BULLETIN



VOL. IV, NO. 6

H. K. WITHERSPOON, Editor

August, 1923

# Chimney Rock Highway Reconstructed

By C. F. Niles, Resident Engineer

N ORDER to appreciate the work involved in the construction of a hard surfaced road over this link in the Charlotte-Asheville Highway, one should be familiar with the locality. This road begins in "The Chimney Rock Country" at the Rutherford-Henderson County Line and goes into the "Hickory Nut Gap Country," to the Henderson-Buncombe County Line It is essentially a tourist section as the land is so mountainous and rocky that farming is not an industry but a necessary evil to the people. The mountaineers of this region raise a little wheat, rye, corn, and enough cattle and hogs for their own subsistence only. Some of the corn is used for bread but it is said there are other ways of consuming corn in these mountains. During the summer months tourists visit this section of Western North Carolina in large numbers and leave enough wealth to make it possible for the local people to exist the rest of the year. Nearly every cabin is a boarding house of more or less pretension. The country offers various amusements to tourists, such as: fishing for rainbow trout, swimming in cold mountain streams, mountain climbing, camping, killing rattlesnakes, etc., and a great many people come here from the states south of us.

As to the road project itself it has a rather interesting history. The people here tell that twice before has it been built by the State. In 1916, a great portion of it was washed away by a terrible flood. In 1917 it was rebuilt by convict labor as Federal Aid Project No. 2, with Mr. Wythe M. Peyton (lately District Engineer in the Ninth District) as Resident Engineer. At that time about sixty convicts were worked for two years or thereabouts constructing the road and wooden bridges. There was little money to spend so the alignment followed the Hickory Nut Creek rather religiously to save grading cost. That road is now very badly worn out and is being rebuilt as a waterbound macadam road with reinforced concrete bridges. The roadway will be twentysix feet wide with eighteen feet of pavement. There will be four bridges two of which will be single spans of thirty and forty feet respectively. One of the others will be four spans of forty feet each while the fourth will be

two arch spans of about one hundred feet each. The latter bridge has not yet been designed or let. These bridges will carry a roadway twenty feet wide paved the entire width.

Mr. J. B. Ross, Jr., of Pickens, S. C., has the contract for the roadway grading, pipe culverts, and paving. His contract was signed June 2, 1923, and work commenced immediately.

Mr. R. C. Stevens of Asheville, N. C. has the contract for the bridges and box culverts. His contract was signed June 7, 1923, and on July first one culvert had been completed.

The work is of very heavy mountainous type. There are sheer cliffs twenty-five to seventy-five feet high with which to deal. Whenever possible they are being avoided but some of them will have to be blasted away. In places the location is perilously hung between precipices and Hickory Nut Creek which is from fifty to one hundred feet lower than the road. These features offer continuous problems and makes the work very interesting from an engineering standpoint.

The new road will not follow the old alignment entirely. It shortens the distance between Chimney Rock and Hickory Nut Gap considerably and straightens the worst of the curves. Even then there will be two places where the road winds back upon itself as it climbs so that the road will be visible three times down the moun tain from the upper level.

The estimated cost of the roadway and bridges is \$255,602.50. It is a safe wager that this estimate will be exceeded, however.

Some benefits to accrue after this project is completed are: quicker motor communication between Asheville and Charlotte, easier transportation for crops and therefore, more crops, more tourists to fleece, more children to be able to go to school and to better schools, more pleas ures for the mountain people now shut in away from the towns, more inter-communication between the people of Western North Carolina and the Piedmont and Coastal portions. The added business brought this section of America's Playground will pay the cost of the road building in a few years.

### Central Highway in Davidson County Under Construction

ROJECT 525 is that portion of the central Highway which extends from the Yadkin River to the city of Lexington, a distance of 10.24 miles. Bids for this project were opened on November 18, 1921; the contract for the roadway was awarded to Elliot & Sons for Standard Topeka Type pavement on December 16,

1921, and the contract for structures to Austin Bridge Company on December 6, 1921.

Grading was started by the former on December 23, 1921, and the pouring of concrete base on May 12, 1922. A stone quarry was opened at the southern end of the project on the bank of the Yadkin River, thus enabling crushed stone to be loaded directly into cars on a siding of the Southern

Railroad and transported to a siding near Lexington for the pouring of base on the half of the project adjacent to Lexington. The other half was poured by direct haul with the trucks from the quarry to the concrete mixer. Approximately 80% of the base was poured with stone from this quarry and the remaining 20% was purchased from commercial quarries. Local sand was used, such pits furnishing

about 75% of the amount required, and the remaining 25% was purchased from commercial pits.

Equipment for pouring of base consisted of Hetzel Forms, Multi-Foote Mixer (21 EM Type), Buffalo Pitts Steam Roller, and various types of trucks which hauled concrete materials from central proportioning plant direct to the mixer, each truck hauling one or more 4-bag batches for a 1: 21/2: 5 mix. Pouring of base was completed on May 17, 1923. The material composing the subgrade on this project is generally a red clay, consequently gets too muddy for pouring with a slight rain fall and dries out slowly, thus necessitating more than the average amount of lost time.

The Topeka surfacing was sublet

to the Harlee-Thrasher Construction Company and
work was begun on November 16, 1922 and carried
on expeditiously and satisfactorily until its completion on May 26, 1923. By the use of two rollers
the laying of asphalt surfacing was permitted during
the winter months. A new 1,200 yard capacity Cummer
plant had previously been set up by the road contractor

at a point about one mile from the city of Lexington, and the surface course was laid from this plant.

The contractor is at present employed in building shoulders, digging drainage ditches, and doing other miscellaneous work in order to complete his contract which should require about two months from the present date.

The work on structures on this project was started on January 3, 1922, and was completed on May 1, 1923. The contract consisted of three "Reinforced Concrete Deck Girder" type bridges at approximate stations 160, 274, and 407, these structures replacing I Beam Spans, a total of 13 spans both 35 and 40 feet for a distance of 522 feet.

On the first structure un-

BRIDGE OVER SWEARING CREEK-PROJECT 525

usual circumstances were experienced with the foundations as all piers and one abutment are supported by a pile foundation while the other abutment is supported by both pile and rock. The main wall of this abutment rests on rock at about 3 feet below elevation shown on the plans. Drilling showed the rock to drop almost vertically downward at approximately the break in the wings with the main

wall. Piles were then driven to a penetration of 13' 0" apparently resting on rock. The same strata again appears in the bed of the stream, when 10' away piles were driven to a depth of 20'. Foundations gave comparatively little trouble; considerable running sand was encountered on a number of piers but the contractor handled this to the entire satisfaction of the Engineer in charge.

One feature of the entire project was the consistency, mixing, and placing of the concrete. The quality of the concrete placed by the contractor was all that could be desired.

The black top surfacing of the roadway was continued across the bridges giving them a smooth even riding surface.

SCENE ON PROJECT 528

The strike of the shopmen on the railroads throughout the country occasioned about two months delay to the contractor on both roadway and structures on this project due to the shortage of material aside from this loss of time another factor was loss of organization.

# Road Work in Hoke County

By L. D. Hicks, Resident Engineer

OKE County is situated in the southern part of North Carolina, a short distance west of Fayetteville, one of the oldest cities in the State. It is bounded on the north by Moore and Harnett counties, on the east by Cumberland county, on the south by Robeson county and on the west by Scotland county.

Hoke county is divided into two distinct physiographic divisions, known as the Sand-hills and the Flatwoods. The Sand-hills, the northern section of the county, is a rolling country of sand, long-leaf pine and "black-jack" oaks. The Flatwoods, the southern section of the county, is a low, slightly rolling, swampy region. In this section lie Projects 544, 545, and 546.

Project 544 consists of 10.3 miles of sand-clay road running almost due south from Raeford to the Robeson county line, and there joining Project 391. This Project, No. 544, is on route No. 70, which runs from the Virginia State Line to Lumberton. The road runs

through some very low, flat, swampy country, necessitating much borrow.

Project 545 consists of 9.1 miles of sand-clay road running almost due west from Raeford to the Scotland county line, and there joins the Sixth District. This road is part of route No. 24 which crosses route No. 70 at the beginning of Project No. 544.

This Project is also in the Flatwoods, but runs through a more rolling territory.

Project No. 546 consists of a Sheet Asphalt pavement, 70 feet wide and about one-half of a mile long, running through Main Street in Raeford, the county seat of Hoke county. This project is really work of the state and city combined, the state paying for 18 feet of the pavement through the center of the street. This Project is also a part of route No. 70, and joins Project No. 544.

Situated as they are in the low, gently rolling section of the Flatwoods, these Projects could have very good alignment. On Project 544 there is one tangent four miles long, the remaining tangents ranging up to two miles in length. Project 545 too, has some very long tangents, the longest being about three miles long.


Whenever curves occur they are usually long easy ones, so slight in degree that banking is unnecessary. There are, however, two banked curves on Project 544,

one occurs on Project 545. There are ten curves on Project 544, three occurring within a half of a mile of one another, and only six curves and one deflection occur on Project 545. Deviation from a straight line is only resorted to when a large swamp area is to be missed, or when it is desirable to cross a stream at right angles.

Since the alignment through this territory is good, it is evident that the grades too, are long and easy. On Project 544 there is one level grade one half a mile long, running through a long bay which is covered with water during the wet seasons of the year. The road through this place is built on an average of a one and one-half foot fill. The longest grade on Project No. 545 is a 0.3% grade for a distance of 3,000 feet. This too, is on a fill.

Drainage in this swampy country is one of the most important factors in the construction of a good

road. Larger openings for drainage structures are required than what the average engineer would estimate on first sight, and the opening necessary will deceive him sometimes even after he has figured the area to be drained. In severa linstances on both of the sand-clay Projects it was necessary for the resident engineer to



SHEET ASPHALT IN TOWN OF RAEFORD-PROJECT 546

change the sizes of pipe, and in one instance on each of the projects, it was necessary to put in a box culvert instead of a pipe. During the dry summer months the streams in many instances dry completely up, while in the extreme wet season of winter and spring, they turn into small creeks, draining some large bay or bays sometimes miles away.

These bays, occurring as they do sometimes, away from the road will back water up on it and cause trouble. In a few instances long ditches are necessary to preserve the road from this danger. One instance of this in particular occurred last winter on Project 545 when one of these bays began to back up into the road, making it necessary to dig a ditch at once to save that portion of the road. The shortest possible ditch to drain this bay had to be 1,500 feet long. In a few instances where a pipe was installed beneath the road long outlet ditches ranging from a few yards to 900 feet, were necessary to drain the pipe.



# PUBLISHED MONTHLY BY NORTH CAROLINA STATE HIGHWAY COMMISSION RALEIGH, NORTH CAROLINA

#### COMMISSION

Frank Page, ChairmanRaleig	h
J. E. CAMERONKinsto	n
J. G. STIKELEATHERAshevil	le
W. A. HartTarbon	0
W. A. McGirtWilmingto	n
JOHN SPRUNT HILLDurha	m
J. ELWOOD CoxHigh Poin	ıt
W. C. WILKINSONCharlot	e
A. S. HanesWinston-Sale	m
A. M. KISTLERMorganto	n
CHAS. M. UPHAM, State Highway EngineerRaleig	h

Address all communications in regard to Bulletin to the Editor, Box 1140, Raleigh, N. C.

This Bulletin will be sent gratis to any State or county official, contractor, newspaper, trade publication, library, or other person interested in the improvement of roads and in the work of the Commission. Advertising rates may be obtained on application.

Volume IV

August, 1923

Number 6

#### Table of Contents

	PAGE
Chimney Rock Highway Reconstructed	3
Central Highway in Davidson County under	
Construction	4
Road Work in Hoke County	5
Editorial	6
Tennessee Governor Inspects N. C. Roads	7
Project No. 272 Opens Trucking Section	8
Hyde County Highway Opens Rich Country	9
Construction of Monolithic Culverts	10
Highway Ordinances Passed by Commission	11
Status of State Work in North Carolina	16
Some Automobile Statistics	12
Advertisements	22

#### Editorial

Bids will be asked on thirteen projects on the 29th of the current month. A number of projects on the list were carried over from previous lettings.

Mr. Thos. H. McDonald, Chief of the Bureau of Public Roads was in the State last month and after an inspection trip expressed himself as being highly pleased with the progress made.

July was an unusually good month for grade crossing accidents, thirty-five deaths being mentioned in one issue of a State paper. There is a "Stop" law in this State but without the use of some common sense by auto drivers it will avail nothing.


The scene on the cover this month is another reason why North Carolinians should "see North Carolina first." The western section of the State is full of such scenes as this and beautiful mountain scenery. The Editor will be very glad to furnish routings and maps free of charge to those desiring to make a trip to the mountains.

Figures recently compiled show that on July 1, 1919 there were under construction and completed 20 projects totalling 132.25 miles of roadway and costing approximately \$1,152,268.86 while on July 1, 1923 there were 440 projects totalling 3,266.31 miles of road and costing in round figures \$58,601,000, 1,327 miles of the latter mileage being paved roads.

# Tennessee Governor Inspects N. C. Roads

ORTH Carolina was honored last month by a visit from Governor Austin Peay, chief executive of our sister state, Tennessee, who spent several days on an inspection trip of North Carolina's highway system and the organization and methods of the State Highway Commission. Tennessee is endeavoring to put over a bond issue of \$75,000,000 for the purpose of building

and maintaining an upto-date system of roads but prior to the election of Governor Peay roadwork was hopelessly mixed with politics, a combination which never has and never will prove anything but a failure. The first act of the present executive was to begin to straighten out the muddle that had existed for so long. The State Highway Commission was abolished and in its place a State Highway Commissioner who knew roads but not politics.



party were met at Hot Springs, near the Tennessee line by a party headed by the State Highway Commissioner who acted as pilot on the trip throughout the State. The roads in the vicinity of Asheville were inspected by the party after which the trip was continued by way of Rutherfordton, Bessemer City and Gastonia to Charlotte where the party spent the night of July 8th.

GOVERNOR PEAY BUYS GAS IN

WAKE COUNTY

The following day a trip was made to Greensboro, via High Point, where a sidetrip was made to the famous Guilford Battle Ground. Thence the party drove to Durham and to Chapel Hill where the Governor was shown over the University campus, after which the party continued to Raleigh for the night.

In spite of the beautiful scenery and the excellent roads which were enjoyed

from the mountains to the capital, the chief interest of the Governor seemed to be in the State Highway Commission building where he was shown the various departments where different branches of highway work are carried on. The Governor took a deep interest in everything, which was evidenced by numbers of questions.

While in Raleigh the Governor and his party were

shown through the Hall of History, the State Capitol, and the State Prison and following a brief visit to Wake Forest left July 11th, on the return trip.

During his brief visit to the State, Governor Peay conferred with officials of the North and South Carolina Commissions with a view to connecting up the systems of the three states. The proposed road system of Ten-



GOVERNOR AND MRS. PEAY ON STATE LINE

nessee embraces approximately 4,100 miles upon which it is expected to spend the proposed bond issue of \$75,000,000. Tennesse has some good roads already but has not a unified system. The State is now working on a county aid system under which the State gets one-half of the automobile and gasoline tax while the remainder is divided among the ninety-five counties of the State. Federal Aid funds are matched one-sixth from State funds, one-third from county funds and the balance from Fed-

eral Aid.

The party consisted of Governor Austin Peay, Mrs. Peay, and Austin Peay, Jr., P. M. Estes, President of the Tennessee Good Roads Association and Mrs. Estes; Mr. Crossling, State Highway Commissioner; Neil Bass, Assistant State Highway Engineer; F. W. Webster, Division Engineer; R. L. Thornton, Federal Engineer;

Cowan Rodgers, Vice-President Tennessee Good Roads Association; R. D. Hanlon, Secretary Knoxville Auto Club; Charles O. Hearon, editor Spartanburg Herald; A. B. Langley, (both members of the South Caroline Highway Commission), Myran T. Nailling, former Secretary Tennessee Good Roads Association; Thos. H. McDonald, Chief of the Bureaus of Public Roads; and S. F. Beatty, Vice-President



WATCHING OPERATIONS OF CORE DRILL

Austin-Western Road Machinery Co.

The first automobile was built and tested fifty years before the first railroad track was laid. Captain Nicholas J. Guinot, in 1769, is credited with having constructed the first motor-propelled road vehicle that actually ran. Steam was the power.

## Project No. 272 Opens Trucking Section

By F. C. Smith, Resident Engineer

ROJECT 272 begins at a point 9 miles from Clinton, on the old Wilmington and Raleigh road, now a section of State Highway route 60, and runs in a southeasterly direction, by way of Delway and Harrel's Store, to the Pender County line. A distance of 16.47 miles.

The contract for this project only calls for the grading, drainage and waterways, however, the contract for the hard surface, which is to be sand asphalt, was called for on February 1, 1923. A satisfactory bid was not received and it was not let, but is to be built by the Highway Commission at an early date.

The territory traversed by this road is one of the least developed sections of Sampson County. On a whole it is a very level strip of land, therefore, making drainage of chief consideration. At times it is very difficult to find fall enough to drain water from the culverts; in some cases it is necessary to

go from 1,800 to 2,500 feet from the road, at which point we can only spill the water over the land. There are long sections which are so near level that it is necessary to dig the fall in the ground. In instances like this a ditch is dug on each side of the road, making center line of the ditch 25 feet from center line of the road. At the beginning of such ditches the depth is usually from one and one-half to two feet deep, with one foot bottom. As the distance and volume of water increases the bottom is widened, always cutting the side slope one-half to one. The amount of ditching that has been required on this project was foreseen, however, and was provided for in the

preliminary estimate, as ditching enough was allowed to construct a ditch 3 feet deep the entire length of the project.

At station 990, what is locally termed "Harvel's Bay" was encountered. This land was no lower than the average along this section, but was so fertile that the gallberry, huckleberry, myrtle and fetter bushes had grown in such masses that it was found necessary to take these up by the roots for a distance of 1,600 feet. This small stretch required more labor per yardage than any similar section on this project. After taking up this mass of roots it was impossible for a team to walk on the mucky bottom, we then had to bring the wheelers to the edge of the fill, and keep a snatch team on the side to dump and pull the team out of the muck. There were times when the snatch team and

the wheeler team were all down, and it was necessary to bring the snatch team from the borrow pit to get them out.

The water ways on this project consist of 19 pipe lines, 41 culverts, ranging from 2x2 to 12x8, and one bridge, consisting of eight 40 foot spans of reinforced concrete with deck girder. This bridge spans six runs at the point known as "Taylor's Bridge." At first sight this bridge might appear to be an excess of what is actually needed. On investigation, however, the fall of the river was found to be such that it brings the water to this point very quickly after a rain fall, so much so that it has been known to overflow its banks to a depth of 4 feet. The grade of this road having been raised, it was deemed necessary to construct a bridge of these dimensions.

The greater part of the material for these structures had to be brought by rail, the nearest railroad station

being Clinton, a distance of 12 miles from site of bridge. The sand, however, was obtained locally, and was pumped from the river bed by means of a locally constructed centrifugal pump, directly connected to an old Maxwell automobile engine.

The advantages of this road, when completed, will be readily seen when its location is taken into consideration. It connects with an improved top soil road to Clinton, which comes under project 275 to be hard surfaced, and also connects with an improved top soil road on the south, leading to Wilmington. The nearest railroad station to any point on this project is seven miles, while the best trucking markets

Type of Drainage-Ditch on Project 272

range from 11 to 15 miles.

This section of Sampson County is especially adapted to strawberries, and one of its natural resources is the huckleberry, better known as "Sampson Blues." They grow wild, and are very prolific in this section. The price ranges upward of \$10 per crate, and has not fallen below \$5 this year. Anyone having had any experience with berries knows the importance of having a good road to transport them over.

Traversing such a sparsely settled and undeveloped section of the county, Project No. 272 is expected to do more than any other one thing for the development and improvement of this section of Sampson County, and we hope ere long to have route 60 so that it will be the main thoroughfare to Wilmington.

# Hyde County Highway Opens Rich Country

HE development of Hyde County into one of the leading grain and cotton producing counties of Eastern North Carolina, has been for some time materially deferred through the lack of sufficient drainage and substantial highways. Now that Mattamuskeet Lake and other large districts are being drained it seems only natural that the State Highway Commission.

sion should have undertaken the construction of a through Highway which will extend for a distance of 19 miles, from the County Seat, Swanquarter, to the Beaufort County line at Leechville.

The section from Rose Bay to Swanquarter was let as Project 151 and construction begun in January, 1922. It was originally intended that this stretch of 4.3 miles should

be elevated for about 5 feet above the average ground surface so as to take care of traffic even during the highest flood levels. Later it was found more advisable to materially lower the grade and at regular intervals, sumps, were introduced to provide an outlet over the road for flood water which would otherwise be impounded, causing inundation of the adjoining farms. Parallel side ditches were excavated by dragline to

provide borrow material for the roadway fill. This type of roadway is still open to improvement and research, however it has certainly proven its value as a drainage factor in swampy country, which is being proven by a noticed increase in the yields of farms adjoining the highway thus constructed.

The present constructed roadway offers an excellent travel medium for summer

and dry weather traffic, but continued heavy rains in the winter season prove very detrimental to the fine sandy loam of which the road in main is constructed. With an idea of suppressing this condition, and of providing a roadway that could be traveled with comfort the "Year Round," the State Highway Commissioner has prepared this project for letting as a hard surfaced highway, which improvement will probably

be started upon the completion of the present grading contract, and pending favorable bids.

The structures on this project were let to Porter and Peck, Contractors of Greenville, N. C., and consisted of ten reinforced concrete box culverts placed at important drainage crossings. These structures have already been constructed and accepted.

From Rose Bay village to Brick House Fork, the roadway is classified as Project 151 Extension. This Project as well as well as Project 151 was awarded to C. W. Lacy, Contractor, Wilmington, N. C., and extends for 3.62 miles from Rose Bay village toward Leechville, and connecting with Project 152.

Excavation is practically completed for one mile, be-

ginning at Rose Bay Creek and extending toward Rose Bay village.

The structures on this project were awarded to O. A. Mann & Co., of LaGrange, Ga., and consist of nine reinforced concrete box culverts, and a seven span (treated) timber bridge, over Rose Bay Creek. A double 12x4 RC box culvert has been substituted for an originally planned 35 foot through girder concrete bridge

over the Drainage District canal at Rose Bay village; the reason being the elimination of an extra high fill through the village. Many of the culverts were built on quicksand foundations. It has been found that after striking the sand strata excavation was almost impossible. This difficulty was overcome economically by letting the sand settle for several days without disturbance; the bottoms of the footing



"Boulevard" Section on Project 151—Roadway not yet Machined



Scene on Project Showing Drainage Canal—Roadway
Incomplete

forms then being floored with rough board.

It has been said that Hyde County is like a jug, this similarity being applicable to inter-county travel possibility, and all such traffic is carried over the one and only route by State Highway No. 91. An improved location of this road connecting Project 151

## Construction of Monolithic Culverts

By I. H. Boggs and C. L. Tindall, Resident Engineers

ORTIONS of Projects No. 200 and No. 201 in Carteret County cross tidewater swamps where bridges are unnecessary and where the flow can be accommodated by large culverts. The water in these swamps is salt; consequenty, it was thought advisable to build monolithic culverts.

For a long time it has been an accepted fact that

salt water is detrimental to concrete. No method of construction nor consistency of mix has yet been found that is guaranteed to completely withstand salt water. It it believed, however, that dense concrete and few if any construction joints will go a long ways towards making concrete impervious.

Eleven culverts on the above named projects are under construction in salt marshes. By a special order from the Bridge Department, these culverts are being constructed of Class "A-A" concrete (1:1½:3 mix) and are being poured as a monolithic structure.

The usual way of pouring a concrete culvert—footing first and bar-

rel and headwalls after the footing has set up—is generally known. The monolithic culvert is rather uncommon and the mode of construction may be noted with interest. The general scheme of construction that is employed by the contractor on Projects No. 200 and No. 201 for building monolithic culverts is a combination of ideas of all concerned as no one on either project had ever seen a monolithic culvert built.

Unfortunately, there is not a stable foundation in any of the salt marshes. First, therefore, it is necessary to drive bearing piles to carry the load. Incondentally, these iles are of great assistance in the construction of a timber floor which has to be built under the entire footing of all the culverts.

The footing of an ordinary culvert, where conditions demand, may be floored with, pine slabs or other cheap lumber, then the

footing poured and allowed to set up before the rest of the structure is completed. The footings of these monolithic culverts, however, must be floored with timber of sufficient bearing capacity to support the weight of the entire structure until the concrete sets up and the loan is transferred directly on the piles.

After the piles are driven, the excavation is shaped up

and carried to an extra depth of about 8 inches to admit the floor stringers which are spiked to the piles. The floor is built with rough timbers the size of which varies with the span of the culvert. The floor under the barrel is made sufficiently wide to permit the side-wall forms to rest on it.

The entire set of forms for the culvert is built in

place on the floor. The outside forms for the wall are braced to poles that are driven securely in the mud eight or ten feet from the structure. The inside or box form is built in sections and then set on the floor and bolted together on the inside. The box form is supported above the floor a distance equal to the thickness of the floor-slab by 1"x2" strips that are nailed to the studding inside the form. (When the box form is removed from the completed culvert, these 1"x2" strips are knocked loose from the studding and cut off flush with the floor-slab.) Planks for the top of the box, or that part which supports the top-slab of the culvert, are cut and fitted but not put in place

until the footing and half the wall have been poured. Access to the footing while the concrete is being poured is thus permitted.

The steel for the footing is wired together in mats and laid on the floor before the barrel form is set in. It is supported in its proper position by being laid on precast concrete blocks or suspended by wires from the stringers in the box form. This steel is best sup-

ported by the concrete blocks. The blocks become completely imbedded in concrete, whereas, wire can be cut off only at the surface of the slab thus permitting an attack for salt water.

Steel for the top slab is wired together, usually in two mats, and laid in the wet concrete after a 3" layer has been poured on the top of the box.

Suspension of the steel in the walls offers no particular difficulty if the brace-wires running

through the walls are so placed that they coincide with the horizontal steel. The horizontal steel may be fastened to the brace-wires and the vertical steel in turn fastened to the horizontal.

After the forms are completed and the steel is in place, the greater part of the job is done. Pouring the con-



SITE OF MONOLITHIC CULVERT BEARING PILES IN FOREGROUND—BUT NOT CUT OFF



FORMS FOR MONOLITHIC CULVERT

(Continued on page 15)

# Highway Ordinances Passed by Commission

NDER and by virtue of the provisions of Chapter 160, Public Laws of North Carolina, Session of the General Assembly, 1923, and particularly Section Ten thereof, and to prevent the abuse of the State highways, the State Highway Commission-of North Carolina does ordain;

Section 1. No houses or other structure or substance weighing in excess of ten (10) tons shall be moved on or over the State highway ,except by special and written permission of the State Highway Commission.

Sec. 2. No lumber, logs, cord wood, or other material shall be placed upon the pavement roadway or shoulders of the State highway, nor shall any material be placed in any manner thereon that will interfere with the drainage of the highway or the maintenance thereof.

Sec. 3. It shall be unlawful for any vehicle, engine, team, or contrivance whatsoever, to move upon any portion of the State Highway or Bridge thereof which has a flange, rib, clamp, or other object attached to its wheels or made a part thereof and which is likely to bruise, injure and mutilate the surface of such road or bridge without written permission first obtained from the State Highway Commission. This Section shall not be construed to prohibit tire chains of reasonable proportions on vehicles when required for safety and arising from conditions tending to cause such vehicle to slide or skid.

Sec. 4. No person shall throw or place, or cause to be thrown or placed upon any highway or bridge, any tacks, nails, wire, scrap metal, glass, crockery or other substance injurious to the feet of persons or animals or to tires or wheels of vehicles. Whoever accidentally, or by reason of an accident, drops from his hand or a vehicle any such substance upon any highway or bridge shall forthwith make all reasonable efforts to clear such highway or bridge of the same.

Sec. 5. No logs, ground sleds, or other objects shall be dragged along or across any portion of the State highway without permission of the State Highway Commission.

Sec. 6. No trucks or other vehicles shall be operated upon the State highway when the tires of which are worn to an extent as to cause damage to the highways because of any defective or worn condition.

Sec. 7. No log cart, or other similar vehicle using a tire of less width than four inches shall be permitted at any time upon the State highway without first obtaining a permit in writing from the State Highway Commission. And no person shall be permitted to transport, discs, or other types of harrows, on the State highway unless ample protection is made to prevent the tooth from cutting or otherwise mutilating the road surface.

Sec. 8. No vehicle shall be operated upon the State highway with two wheels on the edge of the hard surface of any highway, and the opposite wheels on the shoulders thereof, for the purpose of retarding the speed of such vehicle. All vehicles shall be provided with sufficient brakes.

Sec. 9. No motor truck or other vehicle shall be loaded on any road while standing on the roadway and in a manner that will interfere with the traffic thereon or the maintenance thereof.

Sec. 10. No motor vehicle, shall remain on the roadway while being served by a filling station, garage or other service station.

Sec. 11. It shall be unlawful to repair any motor or other vehicle on the surfaced way of any roadway and in a manner which may impede or otherwise interfere with traffic or maintenance of the highway.

Sec. 12. No vehicle or other obstruction whatsoever shall be left standing in the roadway at night unless the same shall be protected by a proper light or lights on the same, and no disabled vehicle shall be left standing upon the highway for a longer period than ten (10) hours.

Sec. 18. It shall be unlawful for the driver of any motor or other vehicle to bring the same to a standstill side by side on the roadway, nor shall any two cars be parked in a manner that will impede or otherwise interfere with traffic upon the highway or hinder or otherwise interfere with the maintenance thereof.

Sec. 14. No advertising or other signs shall be erected on the highway or right of way thereof, so as to obstruct the vision or otherwise increase the hazard, and all signs shall be placed in a manner to be approved by the State Highway Commission.

Sec. 15. No person shall remove, injure or tamper with any signs placed by authorities of the State Highway Commission, or by any other officer or agent acting under its direction; nor shall any person operate any vehicle over a highway or bridge which is lawfully closed for construction or repairs, and contrary to posted notices, whether the work thereon is being done by the State or by a contractor, unless permit to pass is expressly granted by some person in charge of the work.

Sec. 16. The State Highway Commission may designate any portion of the State highway as a light traffic highway and restrict the weight carried thereon to such limit as it may deem proper, figuring on the basis of a given number of pounds per inch width of tire, per wheel or otherwise. Such roads shall be indicated by proper marks and it shall be unlawful, except by special and written permission of the State Highway Commission, to carry any greater weight upon the State highway so designated than that so prescribed and shown on the road signs.

Sec. 17. No vehicle, engine, contrivance, or other object of whatever character shall be moved upon or over any highway or bridge upon wheels, rollers, or

otherwise in excess of the weights prescribed for said light traffic road without first obtaining a written permit from the State Highway Commission.

Sec. 18. No motor or other vehicle having an overall width of more than ninety-six (96) inches shall be operated upon the State highway, unless by special and written permission of the State Highway Commission.

Sec. 19. No private drive or roadway shall be constructed to intersect any portion of the State highway unless adequate drainage shall be provided and in a manner to be approved by the State Highway Commission

Sec. 20. It shall be unlawful for any person to use any part of the road as a turn-row nor shall any person be permitted to plow within the right of way.

Sec. 21. No fence or other object shall be erected on the right of way of the State highway and in a manner that will interfere with the drainage or maintenance thereof, nor in a manner tending to increase the hazard thereon.

Sec. 22. No material of whatsoever kind shall be placed in the ditches paralleling the State highway and in a manner that will interfere with the drainage thereof, and no person shall divert, or cause to be diverted, water into the road ditches and in a manner which may interfere with the drainage of the State highways or in any manner to cause damage thereto.

Sec. 23. No railroad, tramroad, or other road using rail of whatever character, shall construct a track across any portion of the State Highway System unless special permit is granted in writing by the Chairman of the State Highway Commission.

Sec. 24. Whoever operates a motor vehicle at the intersection of highways must keep to the right of the intersection of the center lines of the traveled part of such ways when turning to the left, except when traffic officers otherwise direct.

Sec. 25. No cars or other vehicles shall be permitted to park on bridges or fills constituting any part of the State Highway System.

Sec. 26. No person shall drive through any school zone, or other danger zone, designated on the State highway and at a greater rate of speed than that designated upon such zone signs.

Sec. 27. No vehicle shall be driven at a greater rate of speed than ten (10) miles an hour while crossing any wooden or steel bridge or bridges where warning sign is displayed, having a greater span than twenty (20) feet.

Sec. 28. All rural mail boxes shall be so placed as not to interfere with traffic or the maintenace of the State highway.

Sec. 29. Pedestrians walking on highways shall keep on the left hand side of the road.

Sec. 30. Any violation of the foregoing rules, regulations or ordinances, shall constitute a misdemeanor and be punishable as provided by Statute.

Sec. 31. That the foregoing ordinances shall be in full force and effect from and after July 15, 1923.

Duly read, approved and ratified this 30th day of June, 1923.

The General Assembly of North Carolina do enact: Section 1. That no person, operating any motor vehicle on the public roads shall cross, or attempt to cross any railroad or interurban track intersecting the road at grade, other than a crossing at which there is a gate or a watchman (except an electric railway in the city, town or village) without first bringing said motor vehicle to a full stop at a distance not exceeding 50 feet from the nearest rail. That no failures so to stop, however, shall be considered contributory negligence per se in any action against the railroad or interurban company, for injuries of the person or property; but the facts relating to such failure to stop may be considered with the other facts in the case in determining whether the plaintiff was guilty of contributory negligence.

Sec. 2. That every railroad, or interurban company, operating or leasing any tract intersecting a public road at grade shall place a sign board, not less that 10 feet from the ground, on the right side of the road, 40 inches by 50 inches, 100 feet from said crossing which shall be painted with red lettering, to insure warning of the proximity of the crossing and notice to stop said vehicle, with the following "N. C. Law, Stop"; Provided this act shall not interfere with the regulations prescribed by towns and cities.

Sec. 3. That any person violating the provisions of this act shall be guilty of a misdemeanor and, upon conviction, shall be fined not more than \$10, or imprisoned not more than 10 days, or both, in the discretion of the Court.

Sec. 4. That this Act shall be in force from and after the first day of July, one thousand nine hundred and twenty-three. Ratified this 6th day of March, 1923.

#### Some Automobile Statistics

HE number of motor cars and trucks registered in the United States in 1922 was 12,239,114. The number is about thirteen times greater than it was ten years ago, the number in 1912 being 944,000. Statistics began with 300 in 1895, rising to 28,755 in 1902.

The number for 1922 means one motor vehicle for 8.84 persons in the United States. In California there is one for every 4.29 persons. The actual number of vehicles is greater in New York than in California, but owing to the larger population, there is in New York one vehicle to 10.68 persons.

The number of motor cars and trucks in North Carolina in 1922 was 209,426; that is, one to 12 persons.

The number of motor vehicles made in the United States in 1922 was 2,561,000, while in 1912 the number was only 378,000; so in ten years the yearly production has increased sevenfold.

There were 14,000 persons reported as killed in automobile accidents in 1922.

#### Road Work in Hoke County

(Continued from page 5)

The predominating soil on the surface of the Flatwoods territory, like that of the Sand-hills, is sand. Sometimes this sand ranges in depth from a few inches to several feet. One borrow pit on the sandy end of Project 545 was twelve feet deep, and all of the material was sand. In most cases, however, this sand covers a natural sand clay material, which is an excellent surfacing soil.

No rock ever occurred on either of these Projects, in fact no bids were asked on any. The footings of all bridges are on piles, as the soil will not give the proper bearing power. The absence of rock proved to be advantageous when deep cuts were encountered, as the grading work could be pushed along without blasting or drilling.

Much timber used to grow in this part of the country, but most of it has been cut. Patches of timber are found here and there, and many of the open places

contain huge stumps which are difficult to grub. The farmers have, in many instances, left the stumps standing, letting them decay until they are easier to get out. This fact caused the grubbing on both Project 544 and Project 545 to exceed the amount estimated.

Construction on Project 544, roadway, began in April, 1922. O. A. Mann & Co., of La-Grange, Ga., was awarded the contract, but sublet the work to Mr. J. A. Starke and to Mr. F. P. Holder, both of Ga. Each of these contractors had a force and equipment of about 20 men, 40 mules, 12 wheelers and a road machine.

Unskilled at first, these men were handicapped, but as the work progressed labor and mules were gradually whipped into shape. In addition to the

fact that unskilled labor was used, many other difficulties arose at times. Huge gum and pine stumps, which were encountered in many places, could not be blasted on account of the nature of the soil around them. The soft, loose, sandy soil around the stumps would not give enough resistance to the charge, thereby only shaking the stump or in some instances, only splitting them. This peculiar feature demanded another method of grubbing stumps; so the old hand method was used throughout the entire job.

The nature of the soil had its difficulties as well as its advantages. Sandy cuts and boggy swamps impeded the progress of the mules and men. In some instances

cuts contained almost pure sand throughout their entire depth, tiring out the animals in a very short time, and delaying the work. Bogs were encountered in the swampy part of the country, so bad in some instances that the excavated material for the fills had to be "whipped" in, a method used in order that the mules might remain on the fill at all times.

The advantages afforded by the nature of the soil were enough to offset the disadvantages encountered. Sand in most cases was only two or three feet deep, under which was found a mixture of sand and clay, a material easy to handle under ordinary conditions without much wear on equipment. The smooth level cross-section of the land made it easy on the surveying party, who had to catch grade points between cuts and fills, and cross-section all borrow pits. This fact was also a great help to the grade foreman, who carried the grade between the stakes.



SAND-CLAY ROAD—PROJECT 545

Project 544, as mentioned before, is 10.3 miles of sand clay road, the surfacing being 16 feet wide and all fills and cuts having a width of 30 feet. There were 21,665 cubic yards of roadway excavation and 21,735 cubic yards of borrow, the latter predominating on account of the extremely low and flat places encountered, some of them a half of a mile long. 14,743 sta. yards of overhaul were necessary to soil over two stretches of road, one a long swamp and the other a long stretch of sandy territory. The material was hauled in wagons and wheelers for these places.

The bulk of the work was completed on Project 544 sometime in January, but being an extremely wet season of the year, it was sometime in May before the road could be

cleaned up and shaped for acceptance. Washouts had to be filled, brush burned, ditches cleaned out, and in a few places the surface had to be scarfied and reshaped. A Holt Tractor, belonging to O. A. Mann & Co., and a large road machine were used for this work. Borrow pits had to be drained and shaped in an orderly fashion, and the roadway ditches having become ragged during the winter months had to be re-lined and shaped. After much shaping and finishing the Project was turned over to the State in May, 1923.

The Reinforced Concrete Bridges and Culverts on Project 544 were let in a separate contract from the roadway, the same being given to Chitwood and Carpenter of Charleston, S. C. They began work sometime in May with a force of twelve men. Five of the six culverts were completed by July, and work was started on the bridge across Raft Swamp Creek, a Reinforced Concrete Deck Girder structure of two twenty-five foot spans.

Several difficulties arose during the construction of the bridge. When the footings were excavated to the elevation desired, a hard strata of marl was found. The use of this for foundations for reinforced concrete bridges is not permitted by the Bridge Department; so piles were ordered driven. Strange as it may seem an average penetration of 20 feet was obtained before the pile had the resistance capable of holding a 12 ton load. The marl strata proved to be only a few feet thick. When the piles were driven, the entire Project of six culverts and one bridge was completed by January 1, 1923.

Project 545, Roadway, consists of 9.1 miles of sandclay road, surfacing 16 feet wide and a 30 foot roadway Work on this project began in June, 1922 by O. A. Mann & Co., of LaGrange, Ga., the same contractor who had Project 544, but with his own outfit. The force and equipment consisted of about 20 men, 40 mules, 12 wheelers, 1 Holt Tractor, and two road machines.

This Project, although in the same physiographic division as Project 544, is in a more rolling locality. The first three miles of the Project, near the Drowning Creek Swamp, was the only difficult part of the road to build, as far as grading and soiling was concerned. One cut about 1,000 feet long and 8 feet deep contained nothing but loose sand. This sand was so bad in fact that one would feel the effects of walking through the cut very much when the end was reached. Three and four teams were kept in the shade at all times to relieve teams when they seemed to be suffering from the effects of their labors in this sand. This cut was soiled from ditch line to ditch line, a width of 30 feet, in order that traffic might never have trouble with this sand.

The first four miles of this Project was the swampiest part of the line. In one place, 11,000 cubic yards of borrow was used to construct a fill, 1 mile long, across one of these swamps. Much care had to be exercised in selecting the borrow pits for this fill, in order that they might be drained. This difficulty was overcome by selecting a spot as high as possible, and cutting only about two feet. Much area was necessary for this, but it proved advantageous as water was found at greater depths, and it saved the contractor the expense of digging long ditches to drain the pits.

All of the overhaul on the road was incurred in these first four miles. Being a swampy section, only white, gummy clay was found, but this was not used as it is not as good material as the yellow clay. Two of the pits of yellow clay selected were 120 stations apart and contained some of the best surfacing material used on the project. This material was hauled by means of wagons and four Maney Wheelers, the latter being operated by the Holt Tractor and two men. These wheelers

would automatically cut and load the material, each wheeler carrying about 1 cubic yard of it, which is double the volume carried by an ordinary wheeler. The overhaul on these four miles, the only overhaul on the entire job, amounted to over 85,000 sta. yards.

Grubbing was necessary on this Project, of about 13 acres and was handled in a more satisfactory manner than the grubbing on Project 544. About one-half of it was done with a stump puller, but this proved to be much slower than the method finally adopted on the latter half of the job. The Holt Tractor, equipped with about 200 feet of wire cable, would snatch up and pull off the average tree. Sometimes it was necessary to cut some of the roots of these trees and stumps to do this, but the Tractor proved the best means of grubbing, about 35 stations being done in a week.

The remaining five miles of the road caused few difficulties, all of the excavation being easy to handle, and suitable material for surfacing was found almost everywhere. Heavier cuts were encountered, which meant more yardage per mile of road.

Project No. 545, Roadway, was completed on July 7, 1923, and stands as one of the best pieces of sand-clay road in the State of North Carolina. Long grades and tangents, straight uniform roadway ditches, uniform cross-section, and a smooth easy riding surface are the pleasant features of the road. The best surfacing material that could be found was used, and test-holes dug at intervals of 1,000 feet apart proved that the proper thickness of this material is on the road. The secret of the beauty of the entire Project is that the contractor had a skilled force, and took as much interest in the construction of the road himself as did the engineers; the result is that he has left a piece of road which will be a monument to his credit as long as it lasts.

The Reinforced Concrete Bridge and Culvert work on this project was given to Mr. A. W. McClay of Richmond, Va. The contract called for 10 box culverts and a reinforced concrete deck girder bridge of 3 40 foot spans, the latter now under construction. Although the contract for the bridges and culverts and the roadway was let at the same time, it was October, 1922 before any concrete was poured, due to the inability of the contractor to secure labor and materials.

The only difficulty worthy of note, other than the one mentioned, was encountered when construction began on the bridge across Drowning Creek. This creek is surrounded by a very bad swamp, and keeping the water down within ordinary wooden sheet piling is a difficult job. Two double diaphram pumps were tried at first ,but they were unable to pump the water low enough; so finally a 4 inch centrifugal pump, operated by a Fordson Tractor was purchased. This pump alone handles the water in such a manner that concrete may be deposited in a footing with no fear whatsoever of the cement being washed out of the concrete,

#### Construction of Monolithic Culverts

Continued from page 10

crete is comparatively simple and means nothing more than a good, long day's work. With ample material at the mixer, a good supply of fresh water, and an early morning start, an 8'x4' culvert is completed in twelve

hours with a one-bag mixer. In cool or moderately, warm weather the footing may be poured throughout the entire length of the culvert before a layer in the walls is started, but, if the weather is hot, care must be taken to add a shallow layer of concrete in the walls as the footing progresses. If this layer is not added, the first concrete poured in the footing will have obtained its initial set before the footing is completed and the wall started.

Rubbing of exposed surfaces to remove board marks left by the forms is not permitted. It is believed that concrete is more impervious when the surface is not disturbed by rubbing.



FINISHED CULVERT—FORMS STILL IN PLACE

lightly with a hammer as the concrete is placed to assure a film of mortar next to the forms.

It may be said that monolithic culverts are no more difficult to build than ordinary culverts. They are

more expensive, however, because of the necessity of building a strong timber floor, the extra work in suspending the steel and numerous other extra details the explanation of which is not permitted here because of limited apace.

Great care in every detail is being maintained in the culverts. Only time will tell whether or not monolithic construction is going to lengthen the life of these structures in salt water.

Down in the creek Sleeps Jerry Bass; The bridge was narrow, He tried to pass.

A good finish is obtained by first oiling the forms well before the concrete is poured and then tapping the forms

"The average woman has a vocabulary of eight hundred words." It is a small stock, but think of the turnover.

#### Central Highway in Davidson County Under Construction

Continued from page 4

Project 528 lies between the towns of Lexington and Thomasville a distance of 10.24 miles. The contract for roadway consisting of 6"-8"-6" plain concrete pavement 18' wide was awarded to the Hagedorn Construction Company on September 26, 1922 and structures to J. A. Peterson on September 23, 1922.

Grading was started by the roadway contractor on October 2, 1922 and paving began eighteen days later at a point approximately 2 miles from Thomasville and poured to the town by December 13, 1922, when paving was discontinued for the winter months and resumed on March 26, 1923. During this time the contractors force was employed in grading, laying pipe lines, building headwalls and moving material plant from Thomasville to Lake which is a point on the Southern Railroad centrally located and adjacent to the project. All sand and stone used on this project has been purchased from commercial pits or quarries except about 300 cubic yards of sand obtained from a local pit. These materials are hauled from a central proportioning plant by means of a fleet of 1-ton Ford trucks, and cement is hauled in separate trucks and added to the batch at the mixer. Each Ford truck hauls sufficient material to make a 4½ bag batch of concrete 1:2:4 proportions. Other equipment consist of a Multi-Foote Concrete Mixer (type 21 E), Kelly-Springfield Rollers, and Meta Forms.

Since resuming paving this spring, approximately 5¼ miles have been poured and work is progressing satisfactorily. The outstanding features of this project is

the generally excellent material composing the subgrade, the uniform consistency, and smooth finish of concrete, all of which make for good riding qualities of the finished road.

The Structures on project 528 consist of three Reinforced Concrete Deck Girder type varying from 125 to 167 feet span length. Work on Rich Fork Bridge was begun on October 10, 1922. Considerable delay has been caused by the high water and no little trouble has been experienced on foundations. Here the rock varied above and below the elevations shown on the plans. One abutment alone varied 15' in the dip of the rock, from one end of the abutment to the other. In this case some extra yardage was allowed the contractor while the higher side was blasted to an intermediate elevation determined by the Engineer in charge.

The bed of the stream and for some distance back from the banks the material excavated proved to be loose boulders and sand which gave considerable trouble in sinking the cofferdams which varied from 15 to 20 feet deep. The large amount of highwater and the regular tunnels that led from the bed of the stream very materially slowed up excavating and called for much patience but in the end, a good foundation was obtained. At present Rich Fork Bridge has all the substructure and part of the superstructure. Work is now under way on the substructure of all the bridges and the next three months, all going well will, see structures on project 528 nearing completion.

#### STATUS OF STATE WORK IN NORTH CAROLINA

Projects Under Construction

	COTAMIY	LENGTH	TYPE	ESTIMATED COST	BEGUN	CONTRACTOR
NO.	COUNTY	LENGTH	TIPE	ESTIMATED COST	BEGON	CONTRACTOR
101	Beaufort		P. C.	\$ 145,492.76	1-20-23	Public Service Production Co.
105A	Beaufort		P. C. P. C.	78,839.42 164,301.61	11-11-22   1-19-23	J. I. McGhee Cont. Co. Public Service Production Co.
105B 10 <b>6</b>	Beaufort Bertie		T. S.	58,204.90	9-11-22	J. F. Mulligan Const. CoBoney & Hostetler.
107	Bertie	19.30	Graded	50,127.00	3-14-23	Nello Teer—Atlantic Bridge Co.
110	Camden		R. C. S. A.	134 ,866 .48 100 ,000 .00	7-11-22 4-9-23	State Forces State Forces.
113B 115	Chowan Chowan-			100,000.00	. 4-3-20	State Polices.
	Perquimans	11.83	P. C.	326,304.00	5-15-23	Smith Brothers, Inc.
129 1 <b>31</b>	Edgecombe Gates	8.1	Graded T. S.	40 ,850 .00 135 ,515 .60	9-14-22 8-22-22	State Forces Bacon & Moore—W. D. Murray—Sadler Corp.
132	Gates	10.90	T. S.	63,921.00	8-29-22	J. A. Marrow.
133	Gates-Pasquotank.		Gravel Bit Mac	138,045.77 180,441.92	117-22 11-21-21	C. W. Lacy—Pittsburg Des Moines Steel Co. O. F. Leighton—A. C. House.
137 138A	Halifax Halifax-North-	0.90	& P. C.		11-21-21	O. P. Leighton—A. O. House.
	ampton	12.59	S. C.	131,712.13	51-22	Nello Teer—Richards Bros.
138B	Northampton- Halifax		Bridge	347,188.74	2-28-23	Pensacola Shipbuilding Co
145	Hertford	12.88	Graded	88,161.42	7-31-22	Jameson & Bro.—Atlantic Bridge Co.
147	Hertford-Bertie	17.36	Graded	122,245.86 71,422.28	35-23 1210-21	Nello Teer—Atlantic Bridge Co.
151 152	Hyde	4.30 10.89	T. S. S. C	75,651.40	1-15-23	C. W. Lacy—Porter & Peck. O. A. Mann & Co.
154	Martin	11.27	A. C.	394,153.29	4-17-22	Sou. Willite Paving Co.—O. F. Leighton, Inc.
155 155B	Martin-Pitt Martin	20.01	T. S. P. C.	98,176.65 493,900.40	19-22	J. P. Dicus—J. M. Gregory. W. T. Hadlow.
157 A	Martin	12.50	T. S.	85,813 86	10-18-22	Jamison & Bro.—J. A. Marrow.
157B	Martin	12.50	T. S. T. S.	90,396.24 89,942.43	11-13-22 12-22	J. F. Mulligan Constr. Co.—Batson Cook Co. J. A. Kreis & Co.
159 163{F A 167	Nash		P. C.	409,592.40	6-15-23	Public Service Production Co.
167	Northampton		T. S.	92,444.11	7-17-22	Virginia Contr. Co.—Bacon & Moore.
173	Perquimans-Pas- quotank	7.22	R. C.	239 ,444.70	8-25-22	Williams & Williams.
174	Pasquotank-Cam- den	2.40	Cord	55,818.01	4-3-22	D. E. Williams.
183A	Pitt		P. C.	399,854.40	11-13-22	S. J. Groves & Sons.
183B	Pitt		Bridge P. C.	32,343.30 206,516.42	3-27-22 11-21-22	B. J. Boyles. Public Service Production Co
184 185	Pitt		Graded	31,069.72	3-29-22	J. A. Marrow.
191	Tvrrell	6.91	S. C.	58,594.41	1-20-22	C. W. Lacy—M. M. Jones.
195 196	Washington Washington	14.93	S. C. S. C.	65,619.35 83,632.78	2-28-22 5-15-22	L. M. Lee & Co.—B. J. Boyles. W. N. Thompson.
200	Carteret	13.68	Graded	79,629.00	7-21-22	Eagle Eng. Co.—Batson-Cooke Co.
201	Carteret		Graded A. C.	81,652 62 292,698.06	1-17-23 43-22	Duplin Constr. Co.—Batson Cooke Co. West Construction Co.—A. P. Gilbert.
210 219	Craven Duplin-Lenoir		Graded	148,339.29	6-1-21	Chitwood & Carpenter.
220	Wayne-Dunlin	14.53	A. C.	394 ,301 .05 475 ,321 .55	2-27-23 10-2-22	Union Paving Co.
236(F A 245(143	Johnson	15.67	A. C. P. C.	265,179.53	3-22-22	R. G. Lassiter & Co. Hyde & Baxter.
254	Lenoir		Bridge	73 ,415 32	11-22-22	Roanoke Iron & Bridge Co.
256 263	Lenoir	12 03	Bridges A. C.	57,680.00 289,324.20	1-11-23 3-27-22	Englehardt-Kuehen. Union Paving Co.
264	Craven-Pamlico			27,156.25	7-24-22	Rhyne & Kitchen.
272	Sampson		Graded	98,807.39 96,916.82	6-19-22	R. E. Martin—Striblin—Stauddy & Newell.
273 275	Sampson		P. C. Bridges	8,769.74	2-27-23 4-4-23	Eagle Engineering Co. Rhyne & Kitchen.
282	Wayne	14.22	A. C.	398,168.00	11-11-22	Union Paving Co.
291 291B	Wilson	7.63	A. C. Bridges	203,498.18 12,990.23	1-17-22 4-4-23	P. R. Ashby. Jno. M. Ogden & Co., Road not let.
294	Wilson		Bridge	15.770.80	11-29-22	Stearns Bros.
300	Bladen	11.99	S. C. T. S.	64,911.71 82,028.21	4—8-22 11-21-21	T. W. Chandler—Nello Teer. J. F. Mulligan—Powell Paving & Const. Co.
301 312	Bladen Brunswick	9.77	P. C.	347,319.68	7-5-22	Alabama Conc. Prod. Co.—Batson-Cooke Co.
313	Brunswick	3.44	A. C.	105,706.65	3-15-22	Sou. Willite Paving Co.—Roanoke Bridge & Iron Works.
314	Brunswick		S. C.	109,259.10	2-23-22	Hagedorn Const. Co.
316   317	Brunswick	12.12	S. C. Bridge	80,068.72 19,783.20	8-14-22 11-30-22	B. Frank Price—Batson, Cooke Co. Atlantic Bridge Co.
325	Columbus	11.22	T. S.	105,530.04	113-21	J. A. Kreis-Cornell-Young Co.
326 327	Columbus	13.61 5.2	S. C. S. C.	195,838.19 38,269.44	5-23-22 6-21-22	J. T. Plott—J. A. Kreis & Co. J. A. Kreis.
328	Columbus	7.03	P. C.	219,371.68	12-26-22	L. L. Tindall
340	Cumberland	11.07	P. C.	381,032.02	6-15-22	Alabama Conc. Prod. Co.—Hobbs & Peabody.
342 351	Cumberland New Hanover		A. C. A. C.	177,402.50 189,540.00	10-30-22 1-8-23	A. J. Wardrep. Southern Willite Paving Co.
363	Onslow		T. S.	208,476.95	3—5-23	Newell Constr. Co.—Pittsburg-Des Moines Steel Co.
364A	Onslow		S. C.	44,631.40	3-14-22	R. E. Martin.
364B   376	Onslow		T. S. Graded	99,819.50 94,757.85	6-26-22	A. W. McClay. C. G. Kershaw Const. Co.—Cornell Young Co.
0.0		1 102	,	77,77.00		, the state of the

#### STATUS OF STATE WORK IN NORTH CAROLINA --- Continued

Projects Under Construction (Continued)

		1 _				
NO.	COUNTY	LENGTH	TYPE	ESTIMATED COST	BEGUN	CONTRACTOR
377 378 379	Pender-Duplin Pender Pender	14.12 10 00	S. C. W. B. Mac. S. A.	\$ 76,985.70 213,502.96 100,000.00	3-22-22 7-19-22 5-22-22	R. E. Martin-Hazell-Conerat-Quist Co. C. W. Lacy. State Forces.
380 386-87	Pender	19.8	W. B. Mac. P. C.	162,212.60 647,888.05	3—6-23 9-4-22	C. W. Lacy. James O. Heyworth.
389 391A	Robeson-Colum Robeson		T. S. S. A.	83,463.38 43,332.08	10-26-21 4-3-23	L. A. Chitwood. R. G. Lassiter
391B 392	Robeson	1.06	T. S. T. S.	$\begin{array}{c} 17,433.00 \\ 24,937.00 \\ 23,040.00 \end{array}$	2-26-23 5—1-23	H. M. Beasley. Robeson Co., Com.—E. T. Gwathney.
402 403	Chatham	7.01	T. S. T. S.	33,940.28 66,814.00	81-22 2-27-23 11-15-22	W. N. Thompson. C. G. Kershaw.
412 419	Durham Franklin	12.82	P. C. T. S. R. C.	252 ,582 .00 63 ,021 .97 142 ,637 .77	7-27-22 7-14-22	L. L. Tindall, Jamison Bros.—J. M. Gregory. Pittman Const. Co.
428 429 437	Granville	6.94	P. C. Gravel	261 ,393 00 101 ,031 .26	3-21-23 5-8-23	R. B. Sandidge. F. P. Holder—T. J. Newell.
456 457A	Harnett		Graded Graded	37,459.07 75,398.67	1—7-22 4-12-23	Crawford & Crawford—Nello Teer. Dicus Bros.—Richards Bros.
460	Orange Person	9.87	A. C. P. C.	296 ,835 .55 327 ,171 .35	9-25-22 8-14-22	R. M. Hudson & Co. Porter & Boyd.
463 473 F A 481	Vance Wake	7.83	P. C. A. C.	265,546.60 254,995.34	7-11-22 1-24-22	R. G. Lassiter & Co. Union Paving Co.—P. R. Ashby.
484 485A	Wake Wake	8.79	P. C. Graded	311 ,590 .40 92 ,818 .00	8-23-22 5-4-23	P. R. Ashby-Booz-Lloyd & Co. C. G. Kershaw Construction Co.—T. J. Newell.
486 492	Wake	9.04	T. S. Bit Mac	41,074.00 100,436.13	4-11-23 4-10-22	O. A. Mann & Co. Porter & Peck—A. C. House.
493 494{FA	Warren	3.39	Bit Mac A. C.	77 ,866.80 208 ,130.01	7-27-22 96-22	Porter & Peck. Clifford Engineering Co.
502 512	Alamance Caswell	17.43	T.S. & B.M. T. S.	138,629.97 54,375.53	7-17-22 2-19-23	W. E. Graham—Hanford Bros. J. T. Plott.
522 525	Davidson	10.24	P. C. A. C.	37,856.50 <b>363,850.08</b>	6-29-23 12-23-21	Hagedorn Construction Co. Elliott & Sons & Boggs—Austin Bros. Bridge Co
528 532	Davidson Guilford	11.70	P. C. A. C.	427 ,511 .92 385 ,957 .88	10-2-22 2-1-22	Hagedorn Constr. Co.—J. A. Peterson, Elliott-Sholes Co.
532B 535	Guilford	7.78	Bridges R. C.	24,730.00 277,955.21	15-23 4-19-22	L. M. Lowdermilk. Leaksville Lumber Co.
545 555	Hoke Montgomery	20.55	T. S. T. S.	58,195.06 103,708.00	6—5-22 2-19-23	O. A. Mann & Co.—A. W. McClay. Mayfield Construction Co.—F. P. Holder.
569 570	Moore	22.70	S. C. T. S.	97,151.45 90,804.33	8—1-22 5-22-23 4-18-22	Mayfield Const. Co. A. B. McDonald. Royer-Ferguson Co., Inc.—J. L. Brinkley.
577 578 F A 578 156	Randolph	13.77 7.91 7.98	P. C. P. C. R. C.	422,343.57 308,537.68 266,498.43	5-10-23 4-11-22	Allport Construction Corporation.  Cheatwood & Driscoll.
588 589 590	Rockingham	9.81 2.10	P. C. P. C.	324,975.31 66,092.18	10-30-22 6-15-23	Cheatwood & Driscoll—Atlantic Bridge Co. Geo. R. Martin
593{FA	Rockingham Rockingham-Cas-well	17.98	P. C.	525,393.22	7-11-22	J. A. Kreis.
600 602	Alexander	9.3	Graded Bit Mac	12,530.98 189,329.80	5-26-22 109-22	Bolton Construction Co. W. E. Graham.
606 607	Stanley-Anson		Bridge T. S.	54,759.32 37,098.91	3-23-22 3-21-22	Concrete Steel Bridge Co. Geer & Wilson—Booz-Lloyd & Co.
608 614 F A 615	Anson	7.88 9.20	A. C. P. C.	345,408.58 350,085.07	9-27-22 7-21-22	Lampton & Burks—J. A. Peterson. A. L. Harris—Oliver & Costello Bros.
616	Cabarrus	3 58 8.59	A. C. Gravel	98,741.17 46,024.00	39-23 4-12-23	Thompson-Caldwell—Atlantic Bridge Co. Lee J. Smith—L. M. Lefler.
622 629	Catawba	10.85 7.52	A. C. P. C.	354 ,321 .44 268 ,662 .48	·1-23-22 ·65-22	Union Paving Co. A. L. Harris—R. M. Thurmond & Co.
630B 632	Gaston	6.65 8.50	A. C. R. C.	218,625.00 291,868.94	8—8-22 1—2-22	W. F. McCanless, Hobbs-Peabody Constr. Co. Davis-Wilcox Const. Co.
633B 639	GastonIredell	3.8 10.59	A. C. A. C.	57 ,247 .41 387 ,346 .19	1—6-23 1—2-22	Gaston County. R. M. Hudson Co.—Luten Bridge Co.
640 643{FA 647	Iredell	8.17	Bit Mac A. C.	181,990.82 321,614.81	9-26-22 5-21-23	W. E. Graham. Stearns Brothers. A. L. Harris—R. M. Thurmond & Co.
053	Mecklenburg	7.10 8.84	P. C. A. C.	250,108.15 308,732.43	6—5–22 2–28–22 4—3–22	L. Harris—R. M. I nurmond & Co. Union Paving Co.—Luten Bridge Co. Lampton & Burks.
654 658 F A 659 145	Mecklenburg	$ \begin{array}{c} 10.1 \\ 9.55 \\ 7.03 \end{array} $	A. C. A. C. Graded	302,887.09 266,758.80 36,650.00	10—9-22 4—9-23	Union Paving Co. County Commissioners—Luten Bridge Co.
661	Mecklenburg Richmond Richmond	7.93 9.76 5.77	Graded T. S. A. C.	40,683.41 194,501.23	7-18-22 7-28-22	McDonald & Brooks.  A. J. Wardrep.
665 670 671	Cabarrus-Rowan	4.53 7.34	P. C. A. C.	142,221.53 309,262.14	6-29-22 3-20-23	Harris Construction Company. Thompson-Caldwell Construction Co.,—Atlantic
673	Davidson-Rowan.	.59	Bridge	221 ,353 .00 283 ,460 .61	9-19-22 4-26-22	Bridge Co. Hardaway Contracting Co.—Elliott & Sons. P.R. Ashby—J. B. Murphy.
677 691	Scotland-Robeson . Union	7.11	R. & P. C Bridge	14,520.00	2-13-23	J. S. Brinkley.
				1		

#### STATUS OF STATE WORK IN NORTH CAROLINA --- Continued

Projects Under Construction (Continued)

Projects Unaer Construction (Continuea)								
NO.	COUNTY	LENGTH	TYPE	ESTIMATED COST	BEGUN	CONTRACTOR		
No.	Union	6.05 7.90 8.00 7.75 6.50 11.06 3.53 4.66 11.00 8.90 10.62 11.35 2.00 14.86 9.67 2.22 3.40 3.00 8.90 2.50 13.50 7.83 14.50 5.97 36.00 4.97 2.52 10.12 5.84 5.24 4.89 11.63 1.58 10.35 1.580 15.80		\$ 23,549.13 139,901.30 132,297.33 166,245.20 209,188.98 60,000.00 197,687.38 166,595.00 51,890.66 50,000.00 315,025.81 413,067.27 414,085.43 ****  93,054.48 124,874.75 77,334.01 112,685.76 40,000.00 93,500.00 35,000.00 25,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 154,000.00 184,614.65 174,900.00 85,966.21 78,703.50 330,254.27 198,827.02 185,132.97 58,629.01 153,126.60 60,192.33 404,444.48 34,952.94 281,162.75 145,686.75 204,680.74 91,217.50 188,597.04 239,343.83 42,367.49 152,908.42 146,264.80 94,666.00 230,499.94 354,082.45 100,399.47 144,991.44 95,554.80 50,716.66 99,988.02 143,574.20 126,069.30 409,683.45 144,5313.30 249,546.00 164,126.60 118,186.75 90,871.77 69,100.57 58,340.59 171,200.05 124,354.01 218,940.17 114,026.00 9,000.00 350,175.11				

#### STATUS OF STATE WORK IN NORTH CAROLINA---Continued

Projects Completed

NO.	COUNTY	LENGTH	TYPE	APPROXIMATE COST	COMPLETED	CONTRACTOR
100	Dogufont	10.50	D C	\$ 369,777.70	3-15-23	W. T. Hadlow
103	Beaufort		R. C. R. C.	1,706.75	7-3-22	R. G. Lassiter.
113	Chowan	10.32	Graded	39,743.33	3—1-23	Nello Teer—Gregory & Talbot.
114	Chowan	10.40	Graded	45,064.09	4-14-23	Battershill & Goode—Chandler & Ragland.
125	Edgecombe	15.11	A. C.	426,438.76	4-23-23	R. G. Lassiter.
139	Halifax		Bridge	*20,425.59	8-25-22	Chandler & Ragland—Porter & Peck.
140 160	Halifax FrklinWake-Nash	6 03	Bridge T. S.	*11 ,043 .05 53 ,722 .95	5—5-22 3—7-23	Von Glahn & Talbott.
166	Northampton	.47	Bridge	17,954.75	9-14-22	Chandler & Ragland—Southern Dray Co. W. D. Murrey—Sadler Corp.
175	Pasquotank	9.50	Brick	217,405.72	4-19-23	County Commissioners,
186	Pitt	9.57	R. C.	*248,103.78	85-22	Cheatwood & Driscoll.
209	Craven	2.65	P. & R. C.	*114 ,569 .02	2-15-22	Eagle Engineering Co.
211 218	Craven	9.93	A. C. Graded	288,946.02	5-16-23 $2-24-23$	Union Paving Co.
227	Wayne-Duplin Greene	6.81	A. C.	$egin{array}{c} 92,589.58 \ 239,797.80 \ \end{array}$	1-25-23	C. W. Lacy. West Construction Co.—Union Paving Co.
255	Lenoir	0.82	S. A.	30,384.89	8-18-22	West Construction Co.—Office Paving Co.
280	Wayne	10.01	A. C.	311,352.36	5-12-23	Union Paving Co.
281	Wavne		Bridge	*21,225.49	1-15-23	P. R. Ashby.
338	CumbSamson		Bridge	26,323.99	9-26-22	Roanoke Bridge & Iron Works.
339	Harnett-Cumb	.754	T. S.	19.067.28	8-31-22 2-28-22	Porter & Boyd
3 <b>41</b> 375	CumbHoke Pender	.2	Graded S. C.	*1 ,042.55   68 ,830 .09	11-21-22	W. B. Covington A. W. McClay
388	Robeson	3.35	R. C.	137,009.40	9-28-22	C. W. Lacy—Roanoke Bridge & Iron Co.
100	Chatham		Bridge	57,420.22	5-18-23	R. M. Walker & Co.
409	Durham	0.5	Graded	*5,409.10	8-7-22	J. P. Dicus.
110	Durham	2.3	R. C.	*81 ,105 .75	9-28-22	C. D. Riggsbee.
411	Durham	5.81	P. C.	211,574.92	7-12-23	Hutton Engineering and Construction Co.
120 127	Franklin	1.56	R. C. A. C.	$55,421.30 \mid 178,257.64 \mid$	5-29-23 1-4-23	Chandler & Ragland, R. G. Lassiter & Co.
436	Harnett	21 G1	Gravel	202,563.88	1-15-23	C. G. Kershaw Const. Co.—Hobbs & Kitche
445	Lee		T. S.	18,692.85	1-15-23	C. B. Hester.
146	Lee	5.90	A. C.	197 ,188 .22	1-15-23	Atlantic Bitulithic Co.—O. A. Mann & Co.
153	Orange		Bridge	33,706.80	1-9-23	Geo. W. Kane.
154	Orange	4.28	P. C.	197,675.32	3-6-22	Elliott, Sholes & Teer.
155	Orange	4.19	T. S. A. C.	*55 ,214 .44 *184 ,393 .31	9-28-22 9-23-22	J. F. Mulligan Const. Co.—P. R. Ashby.
182 183	Wake	$\begin{array}{c} 6.64 \\ 0.54 \end{array}$	R. C.	*15,630.74	8-7-22	R. M. Hudson Company. C. D. Riggsbee.
500	Alamance	5.22	Graded	*36 ,844 .34	1-17-22	W. W. Tuck & Son—A. M. Hazell, Connerate
						Quist Construction Co.
501	Alamance	13.1	T.S.	30 ,927 .27	2-28-23	W. M. Shook-Hanford Bros.
503	Alamance		Bridge	59,450.38	7-20-23	Atlantic Bridge Co.
504	Alamance	5.22	A.C.	154,127.16   *15,229.74	5-3-23	Elliot & Sholes.
505 511	Alamance	0.42	S. A. T. S.	73 ,242 .18	6-23-22 10-11-22	Hedrick Construction Co. White & Simpson-C. B. Hester
524	Davidson	0.3	S. A.	*9,941.54	1-20-22	Town of Lexington.
525A	Davidson	.5	S. A.	*16,419.86	6-27-21	Town of Lexington.
526	Davidson	3.77	P. C.	*131,269.66	10-25-22	Hagedorn Constr. Co.—Heilig & Sherrill.
533	Guilford-Forsyth	10.59	P. C.	427,997.62	7-23-23	Royer-Ferguson Construction Co.
538	Guilford	0.64	Bridge	7,039.01	2-21-23	J. L. Brinkley.
539 540	GuilfordGuilford	$0.64 \\ 18.00$	S. A. Recon.	$21,639.20 \ 16,527.54$	1-19-23 1-23-22	Robt. G. Lassiter & Co. J. T. Plott.
544	Hoke	10.45	S. C.	32,445.49	53-23	O. A. Mann & Co.—Chitwood & Carpenter.
546	Hoke	0.84	S. A.	27,949.00	5-30-23	Dawkins Construction Co.
566	Moore	7.14	T. S.	62,079.21	6-30-23	Gibson Construction Co.—Nello Teer.
567	Moore	2.96	T. S.	*9,967.53	9-18-22	C. E. Teague.
601	Alexander	3.07	T. S.	33,630.45	3-31-23	Guss Ginn-R. M. Thurmond
330A   333A	Gaston	$\begin{bmatrix} 3.02 \\ 13.77 \end{bmatrix}$	A. C. A. C.	*98,854.41 180,000.00	$722 \ 10 - 5 - 22$	W. F. McCanless, Gaston County
34	Gaston	Bridge	Recon.	4,500.00	10-5-22	State Forces.
38	Iredell	7.88	A. C.	262,142.65	1-20-23	Thompson-Caldwell Co.
52	Mecklenburg		Bridge	1 ,923 .28	10-30-22	State Forces.
55	Mecklenburg	1.57	P. Č.	63,695.17	7-31-22	Speed-Parker Co., Inc.—Luten Bridge Co.
56	Mecklenburg	10.4	BitMac.	200,000.00	10-30-22	State Forces.
57 92	Mecklenburg	$\begin{bmatrix} 13.80 \\ 2.28 \end{bmatrix}$	Recon. A. C.	20,000.00 *65,279.20	10-30-22 12-28-21	State Forces. Redmon Construction Co.
93	Union	$\frac{2.28}{1.14}$	Gravel	3,324.48	14-28-21	Sykes-Collins Co.
95	Union	4.51	A. C.	*138,738.07	9-14-22	Redmon Construction Co.
10	Ashe		P. C.	*142,707.93	8-17-22	Pittman Construction Co.
19	AsheCaldwell		Bridge	*7 ,906 .87	6-26-22	Cottrell & Howard.
19B	Caldwell	.99	Gravel	1,665.33	11-15-22	J. G. Bumgardner
22	Caldwell	7.40	Recon	*20 ,923 .25	1-18-22	County Forces.
724 725	Caldwell	4.66	T. S. Recon	$51,890.66 \\ 28,015.46$	$\begin{vmatrix} 4-13-23 \\ 2-24-23 \end{vmatrix}$	County Forces—R. M. Thurmond & Co. County Commissioners.
701	Caldwell	$\begin{bmatrix} 4.00 \\ 5.46 \end{bmatrix}$	P. C.	195,393.11	7-21-23	G. R. Martin—Heilig & Sherrill.
3	- CUY1U. 0 0 7 0 0 1 0 0 0 0 0		m a		10-4-21	W. E. Graham.
51	Stokes.	7.16	T. S.	*35 ,124 .08	10-4-21	w. E. Granam.
31 51 60 64	Stokes	$\begin{bmatrix} 7.16 \\ 6.9 \end{bmatrix}$	T. S. T. S.	*32,084.18 50,588.20	10-4-21 $11-5-22$ $2-4-23$	W. E. Graham. Leaksville Lumber Co.

#### STATUS OF STATE WORK IN NORTH CAROLINA---Continued

Projects Completed—Continued

NO.	COUNTY	LENGTH	TYPE	APPROXIMATE COST	COMPLETED	CONTRACTOR
li						
H						
801	Avery	.99	W. B. Mac	\$ 22,350.24	10-26-22	Geer & Wilson.
814	Burke		S. C.	13,459.60	4-25-23	M. A. Kollock.
823	Cleveland		P. C.	*80,421.65		Southern Paving Co.—Z. B. Weathers & Son.
844	McDowell		P. C.	*61,233.34	12-13-21	Bolton Construction Co.
845	McDowell		Gravel	132 ,177 .93	12-22-22	J. W. Stapp Constr. CoPraytor, Howton&Wood
855	Mitchell		P. C.	174,393.78	4-17-23	Fisk-Carter Construction Co.
855B	Mitchell		Bridge	*22,699.85	8-22-22	Luten Bridge Co.
866	Polk	5.96	Bit Mac	180,393.40	11-21-22	Southern Paving Co.—Henry Constr. Co.
875	Rutherford		Bridge	*6,151.61		Geer & Wilson
877	Rutherford		T. S.	64,563.73	8-7-22	Geer & Wilson.
878	Rutherford		T. S.	44,984.50	10-27-22	Michaux Const. Co.—Geer & Wilson.
879	Rutherford		Bridge	*6.781.99	6-21-22	Austin Bros. Bridge Co.
880	Rutherford			24,679.43	3-23-23	Austin Bros. Bridge Co.
904	Buncombe		A. C.	80,969.13		Asheville Paving Co.—R. C. Stevens.
910	Cherokee		Gravel	76,743.59	2-24-23	Ross Bros. Constr. Co.—W. T. Moore Concrete.
1010	Character	1.00	Grave.	10,110.00	2 21 20	Prod. Co.
942	Haywood	0.57	Gravel	*6,490.43	2-1-22	O'Brien Construction Co.
1012	Itay wood	0.01	CITAL A CI	3,100.40	2 -1-22	O DIGH COHAM GONOH CO.

#### PROJECTS UNDER CONTRACT

NO.	COUNTY	LENGTH	TYPE	APPROXIMATE COST	CONTRACTOR
141	Halifax-Edgecombe	18 76	T. S.	\$ 220,679.58	J. P. Dicus—J. A. Peterson.
146	Hertford-Bertie	6.42	$\tilde{T}. \tilde{S}.$	60,772.14	Atlantic Bridge Co.—Nello Teer.
168	Northampton		$\hat{\mathbf{T}}.\hat{\mathbf{S}}.$	107,229.87	Nello Teer,
189	Pitt		P. C.	210,247.07	Smith Bros., Inc.—Pittsburg Des Moines Steel Co.
213	Craven		A. C.	447,053.53	F. G. McGuire & Eagle Engineering Co.
230	Greene		P. C.	220,576.18	Smith Bros., Inc.—Pittsburg Des Moines Steel Co.
291C	Wilson	.31	Grade	15,532.00	C. S. Wheeler,
293	Wilson	8.99	P. C.	384,222.08	Smith Bros,. Inc.—Pittsburg Des Moines Steel Co.
295	Wilson		Recon.	124,060.64	Highway Engineering and Construction Co.
329{F A	Columbus	12.88	A. C.	422,462.60	Jas. L. Hayworth.
400A	Chatham		Grading	5,400.00	C. B. Hester. (fill)
431	Granville	3.83	T. S.	$\frac{42,895.71}{1}$	Michaux Construction Co.
438	Harnett	3.82	P. C.	152, 114.88	J. M. Gregory—T. J. Newell.
464	Person	11.58	T. S.	86,268.71	Michaux Construction Co.
484B	Wake		Bridge	13,060.19	Booz-Boyd & Co.
485C	Wake		Grading	10,452.00	Nello Teer. (fill)
506A	Alamance	.32	Grading	9,866.45	Nelo Teer
532C 541	Guilford		P. C. Bit. Mac.	12,650.00 $119,469.24$	W. B. Kiker.
556	Guilford	3.07	Bit. Mac.	78,821.60	Hagedorn Construction Co. J. F. Mulligan Construction Co.
608B	Montgomery		Grading	48,646.51	Ben. F. Teeter—J. A. Peterson,
672	Rowan.		A. C.	167,756.27	Stearns Bros. IncJ. A. Kries.
702B	Alleghany		Gravel	191,737.26	Turner-Hartsoe-Luten Bridge Co.
802	Avery	5.68	Grading	98.043.44	Hughes & Rae.
837B	Henderson		A. C.	83,113.14	Dixon Construction Co.
882B	Rutherford		Bridge	10,582.00	Michaux Construction Co.
930A	Graham		Gravel	12,243.00	C. M. Dicus.

#### STATUS OF FEDERAL AID WORK IN NORTH CAROLINA

#### Projects Under Construction

NO.	COUNTY	LENGTH	TYPE	APPRO	XIMATE COST	BEGUN	CONTRACTOR
15 61 69 94A 125A	Guilford New Hanover Transylvania Mitchell. Alleghany	$9.348 \\ 5.04$	Bit. Mac. P. C. W. B. Mac. W. B. Mac. Bit. Mac.		5,441.75 234,841.39 231,409.04 190,375.13 153,899.13	3-25-20	County Commissioners. C. W. Lacy. Allport & Alexander Construction Co. Gibson Construction Co. W. E. Graham.

R. C.       67, 92       2, 433, 241, 08          A. C.       282, 71       9, 663, 837, 76          S. A.       20, 90       243, 332, 08          Bit. Mac.       51, 40       1, 248, 598, 28       9, 19       159, 340, 88         W. B. Mac.       150, 24       2, 701, 553, 52       14, 39       421, 784, 17         T. S.       368, 31       2, 745, 890, 19        421, 784, 17         S. C.       154, 74       1, 191, 426, 35           Gravel.       190, 53       1, 834, 431, 71           Graded.       245, 56       1, 922, 127, 69           Recon.       22, 33       179,000, 00           Cord.       2, 40       55, 818, 01           Bridges.       981, 069, 56            P. C.       45, 94       1, 800, 931, 52       26, 56       \$ 889, 940, 6°         R. C.       29, 48       959, 343, 62           P. C.       45, 94       1, 800, 931, 52       26, 56       \$ 889, 940, 6°         R. C.       29, 48       95	WORK UNDER CONTRACT	Summar	<i>y</i>			
Length   Cost   Length   Cost			STA.	CNE	F	EDERAL AID
A. C. 32.68 1,120,385.54 BBI Mac. 7.38 198,290.84 ST. S. 198,290.80 ST. S. 198,290.8	Type	Length		Cost	Length	Cost
WORK UNDER CONSTRUCTION	A. C Bit. Mac T. S. Gravel. Graded. Recon.	32.68 7.38 56.89 9.41 10.65 9.92	\$	1,120,385.54 198,290.84 517,846.01 203,980.26 187,940.40 124,060.64		\$
P. C.       330.09       \$ 10,641,722.82       2.19       \$ 234,841.33         R. C.       67.92       2,433,241.08 <t< td=""><td>Total</td><td>150.94</td><td>\$</td><td>3,355,956.09</td><td></td><td></td></t<>	Total	150.94	\$	3,355,956.09		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	WORK UNDER CONSTRUCTION					
$ \begin{array}{ c c c c c c c c } \hline \textbf{WORK COMPLETED} \\ \hline P. C & 45.94 & 1,800,931.52 & 26.56 & 889,940.6 \\ \hline R. C. & 29.48 & 959,343.62 & & & \\ A. C. & 97.80 & 2,806,484.73 & 42.29 & 1,521,368.2 \\ S. A. & 3.52 & 121,564.23 & 22.91 & 763,048.8 \\ \hline Bit. Mac. & 16.36 & 380,393.40 & 30.62 & 798,895.0 \\ W. B. Mac. & 99 & 22,350.24 & 14.00 & 303,505.7 \\ \hline Brick & 9.50 & 217,405.72 & & & & \\ T. S. & 95.91 & 585,191.31 & 509.18 & 5,228,132.5 \\ S. C. & 32.70 & 114,735.18 & 83.90 & 785,198.2 \\ \hline Gravel & 39.36 & 522,965.64 & 42.56 & 488,699.16 \\ \hline Graded & 43.17 & 226,090.69 & 29.23 & 252,426.16 \\ Recon. & 43.20 & 89,966.25 & & & \\ \hline \end{array} $	R. C. A. C. S. A. Sit. Mac. W. B. Mac. T. S. S. C. Gravel Graded. Recon.	67.92 282.71 20.90 51.40 150.24 368.31 154.74 190.53 245.56 22.33		2,433,241.08 9,063,837.76 243,332.08 1,248,598.28 2,701,553.52 2,745,890.19 1,191,426.35 1,834,431.71 1,922,127.69 179,000.00	9.19 14.39	
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	Total	1,887.13	\$	35,242,049.05	25.77	\$ . 815,966.44
	WORK COMPLETED  P. C R. C. R. C. S. A. Bit. Mac. W. B. Mac. W. B. Mac. Brick T. S. S. C. Gravel. Graded. Recon.	29.48 97.80 3.52 16.36 .99 9.50 95.91 32.70 39.36 43.17	\$	959,343.62 2,806,484.73 121,564.23 380,393.40 22,350.24 217,405.72 585,191.31 114,735.18 522,965.64 226,090.69 89,966.25	42.29 22.91 30.62 14.00 509.18 83.90 42.56 29.23	\$ 889,940.67 1,521,368.25 763,048.82 798,895.02 303,505.78 5,228,132.54 785,198.22 488,699.18 252,426.17 651,051.10

Total Roadway Mileage 3,323.02. Total estimated cost of Roadway \$57,267,897.01. Total estimated cost of Bridges \$1,975,097.46. Corrected to August 1, 1923.

#### LEGEND

P. C.—\*Plain Concrete. R. C.—\*Reinforced Concrete. A. C.—\*Asphaltic Concrete. S. A.—\*Sheet Asphalt. Bit. Mac.—\*Bituminous Macadam. W. B. Mac.—\*Water Bound Macadam. T. S.—†Top Soil. S. C.—†Sand Clay. Gravel—†Gravel. Graded—†Graded. Recon.—†Reconstruction. Cord.—†Corduroy.

<sup>\*</sup> Hard Surface. † "G" Type.



On the Famous Corduroy Traction The "Tread" Mark of P & H Excavators

# GLANCE OVER THIS LIST OF P & H SHOVELS FEATURES

- 1. The P& H crowding motion is controlled independently of the hoisting effort, all the power available at any dipper position.
- 2. The P & H crowd is sufficient to allow dipper stick to be extended when dipper is in highest loaded position. The dipper can be pushed out as it breaks through top of bank.
- 3. The power back of the P & H crowd and the de sign of the P & H crowding mechanism allows raising the dipper above boom point sheave: After cutting thru top of bank, dipper of P & H Shovel can be extended to load wagon or truck.
  - 4. The P & H has large digging radius.
  - 5. Dipper moved backward and forward rapidly.
  - 6. Simple rugged fool-proof mechanism.

These features are fully explained in the new Bulletin 58-X, and scores of photographs showing how contractors are using P & H excavating equipment are also included. Tell us where to send your copy.

#### PAWLING & HARNISCHFEGER CO.

Established in 1884

3853 National Ave., Milwaukee, Wis.

SALES AGENTS: Tractor & Machinery Sales Company, 1631 W. Broad St., Richmond, Va.



#### **GASOLINE SHOVEL**

MAIL THIS COUPON

Pawling & Harnischfeger Co., Milwaukee, Wis. Send me copy of new Bulletin 58-X.

Name		 	 
Address		 	 
City & St	ate	 	 

### Hyde Highway Opens Rich Country

Extension to the County line at Leechville, has been classified as Project 152, and shortens the present road of nearly 14 miles to 10.9 miles. Structures and roadway were both let to O. A. Mann & Co., of LaGrange, Ga., in November, 1922. Construction was begun on the roadway in February, 1923, and is now well under way. Borrow fills across Leechville and Scranton marsh es are to be constructed with narrow gauge dump car equipment. Excavation and loading with Keystone Excavator. In order to get an early start on the Leechville Marsh fill, the contractor began work there as soon as his excavator arrived using mules to pull the dump cars; two 2-yard cars to the mule. This method was possible on account of the flat grade of the track, and will probably be continued until a more modern means is devised.

A large portion of the lower end of the Project is being constructed on the "Boulevard," section, a side borrow extending from the shoulder of the road to a back sloped side ditch about 30 feet from center line. This method used as means of abolishing borrow pits, and to facilitate side drainage. The entire width of road when machined, presents the pleasing appearance of a wide boulevard, hence the name.

Treated timber structures are to be enstructed over Rutman's, Wilkinson's, and Broad Creeks. Test piles have been driven to determine length of piling necessary for safe bearing pressure; this having run between 40 and 30 feet. A treated timber bridge with steel draw span is to be built over the Pungo River at Leechville connecting Project 152 with Beaufort County. This bridge to be built by the State Forces.

### Road Work in Hoke County

if a little care is exercised in placing forms. At the present writing almost all of the substructure of the bridge is finished, and with good luck the contractor will complete the structure in about 60 days.

Project No. 546 is a Sheet Asphalt Pavement on a 5-inch concrete base, and was built in conjunction with the city who paid for all work other than the 18 feet through the center of the street. This is the Main Street in Raeford and was built 70 feet wide with curb and gutter. The city employed an engineer for their part of the work, but everything in the way of paving was done as per the specifications of the N. C. State Highway Commission. This Project was started in December, and owing to the extremely mild temperature of this particular locality, no stops were made on account of cold weather. The contractor, Dawkins Construction Corporation of Norfolk, Va., completed this Project, one-half of a mile in length, and several connecting streets by the first of June, 1923.

Much road construction has been completed in Hoke County since April, 1922, and the result is that the county has 30 miles of good highway, 10 miles having been built in 1920-1921. There remains only one stretch of road to be built, which when done will give Hoke County her share of State Roads, according to the schedule of the Commission. This road, from Raeford to the Hoke-Moore county line, at present, is in a good condition.

# Which Are You Going to Pay?

50c PER YARD for shoveling crushed stone into trucks by hand? A good man can load 12-15 cu. yds. in 10 hours—it will cost you 25c per yard for labor alone. And don't overlook the other 25c that it's costing to hold your truck waiting for this slow method of loading.

DON'T make the mistake of figuring on the old fashioned hand loading. Someone will bid in the contracts on a lower estimate and still make a long profit by being wise to the economies of hand loading.


There's a little bulletin "How Haiss Truck Loaders Make Roadbuilding More Profitable" that has honestto-goodness facts in it. Want a copy?

George Haiss Manufacturing Co., Inc.
Canal Place & E. 144th St., New York, N. Y.

Tractor & Machinery Sales Co.

1631 W. Broad St., Richmond, Va.

Or 15c PER YARD with a Haiss Truck Loader. You can do it. First it's a one-man job—the Loader does all the work, feeds the buckets, elevates the load and keeps digging into the pile. Man and machine will average 1½ yards per minute as long as you keep your trucks moving.



# Washed and Screened Sand Gravel Crushed Stone

Conforming to the specifications of the North Carolina
State Highway Commission

Prompt shipments by rail or water

Favorable freight rates to all North Carolina points

Quotations gladly furnished on request

### THE ARUNDEL CORPORATION

MAIN OFFICE:
Pier 2 Pratt St.
Baltimore, Maryland

BRANCH OFFICE: 519 Board of Trade Bldg. Norfolk, Virginia

# Reliability Service Osgood

7

Three words of great importance to the user or prospective user of Steam Shovels. *Osgood* Steam Shovels are built reliable—right in our own factory



OSGOOD ¾ yd. H. D. Grading Highway in Indiana

—to give long and satisfactory service in the field.

An Osgood can only be fully appreciated after it has been seen. Watch one at work. Our new Bulletin 231 will tell you more about them.

34-1 and 114 yd. Revolving type Steam Shovels, Clamshells, Draglines 11/2 to 6 yd. Rai road type Steam Shovels.

### The OSGOOD COMPANY

MARION, OHIO, U.S.A.

# "Standard" Paving Asphalt

has been successfully used on some of the most important highway projects in North Carolina.

This asphalt is refined from the straight Mexican asphaltic base petroleum, its purity being over 99.8%. "STANDARD" PAVING ASPHALT meets all the tests of a paving cement for asphalt concrete or sheet asphalt pavement, its uniformity and ability to resist extremes of temperature making it especially suited for these types of construction.

"STANDARD" PAVING ASPHALT has been used in practically every large city in the east.

# STANDARD OIL COMPANY

(NEW JERSEY)

Baltimore, Md.

Charlotte, N. C.


Newark, N. J.

Richmond, Va.

REFINERIES: Bayonne, N. J., Baltimore, Md., Charleston, S. C.



# Long Years of Life Ahead of Them



# National Lock-Joint Cast-Iron Pipe

The Pipe of Short Units, Long Service and Low Costs

The Pipe that locks effectively, that prevents Separation and assures alignment to perfection.

The pipe which solves culvert renewal problems with least expense, greatest efficiency. The pipe that does not rot or disintegrate, the pipe that is mechanically correct and has proved itself the solution of the culvert problem.

#### CONTRACTORS and ENGINEERS, GET THIS:

TWO MEN, without the use of any tools whatsoever, will unload, handle and install all sizes up to and including 36 inches in diameter.

It is as cheap to handle and install as clay pipe WITH NO BREAKAGE LOSS. In shallow trench work the entire culvert can be built up, interlocked and rolled into place in one operation.



AMERICAN CASTING CO.

Birmingham, - - Alabama



N twenty years Portland cement has advanced from comparative insignificance to the leading position in the construction material field. The ready adaptability of Portland cement to every kind of construction, from fence posts on the farm to gigantic dams and highways of endurance; the facility with which it can be handled; its durability which gives the highest degree of permanence, backed up by constant attention to perfection in manufacture and the most intelligent and comprehensive educative and advertising work that has ever been given to any building material, all combine to account for the remarkable progress achieved by the Portland cement industry. We take just pride in having always kept faith with the sound principles followed by this great industry.

Every requirement for the manufacture of the high standard of quality laid down by the established scientific standard specifications is rigidly followed in making Clinchfield Portland cement. Service in the fullest meaning of the word is our watchword in dealing with our customers.

Builded upon this firm foundation of quality and service the Clinchfield plant has steadily grown and expanded and its products have been used with constant satisfaction for all classes of construction work in the South.

# Tractor & Machinery Sales Co.

Distributors
RICHMOND, VIRGINIA



Dependability!

Economy!

Satisfaction!

There's Only One "CATERPILLAR" Holt Builds It

# The National Cement



FOLLOWING closely the natural demand for cement, and offering advantages in the way of service and shipping facilities, are the sixteen great Lehigh mills stretching from coast to coast.

This nation-wide distribution makes Lehigh Cement readily available to practically any locality, thus insuring uniformity of material and prompt delivery to any job. Lehigh's square-deal policy is added assurance of satisfaction in the use of Lehigh—The National Cement.

16 MILLS FROM COAST TO COAST



### LEHIGH PORTLAND CEMENT CO.

CHICAGO, ILL.

ALLENTOWN, PA. SPOKANE, WASH.

NEW YORK CITY BUFFALO, N. Y. MASON CITY, IOWA MINNEAPOLIS, MINN. BOSTON, MASS: OMAHA, NEB. RICHMOND, VA. BIRMINGHAM, ALA. PHILADELPHIA. PA. KANSAS CITY, MO. NEW CASTLE, PA. PITTSBURG, PA.

# CRUSHED STONE

for

**CONCRETE PAVEMENT** 

for

TOPEKA OR WARRENITE SURFACING

for

**CONCRETE BRIDGES** 

for

CONCRETE WORK OF ANY KIND

For Delivered Prices in Any Quantity
Wire, Write or Phone

ORINOCO SUPPLY CO.

WINSTON-SALEM, N. C.



#### Loading End Strains

HINK of strains that the loaded fast-moving skip puts on the mixer frame! How they must tug and twist at the frame! Hundreds of times every working day. Thousands of times every season!

Now look at the Koehring frame construction—how the frame is braced, and re-inforced against strains and stresses from every direction. This is one reason why Koehring driving parts do not get out of alignment and set up unusual wear, breakages and delays. Get this Koehring "Heavy Duty" construction fixed in your mind, and recall it when you think about mixers.

#### EARNEST BROS.

RICHMOND PHONES MADISON 6460 MADISON 1381

805 E. Franklin St.

BRANCHES RICHMOND, VA. CHARLOTTE, N. C. RALEIGH, N. C.

"Earnest Service by Earnest Bros."

#### KOEHRING CAPACITIES

Pavers: 7, 10, 14, 21, 32 cu. ft. capacities mixed concret e steam and gasoline. Write for catalog P-19.

Construction Mixers: 10, 14, 21, 28 cu. ft. mixed concrete, steam and gasoline. Write for catalog C-19.


Dandle: A light staunch mixer for footings, culverts, foundations, etc. 4 and 7 cu. ft. mixed concrete, steam and gasoline. Power charging skip, low charging platform batch hopper, light duty hoist. Write for catalog D-19 Rubber tires optional.

#### OTHER PRODUCTS:

Koehring Cranes and Shovels Blaw Knox-Forms

Turntables Bins and Batchers Clamshell Buckets

C. H. & E. Pumps PARSONS Excavators JEFFERY Loaders



# TRUCK ROLLERS that LAST!

THE DRIVING WHEELS of the most powerful locomotives have forged steel rims.

The Truck Rollers of a track type tractor support the weight of the tractor and the flanges of rollers must withstand severe jars and side strains of side hill work and rough going.

On Best Tractors the flanged rims of truck rollers are drop forgings-nothing less-forged into shape under heavy steam hammers, from heated steel of special analysis. After being forged the rims are annealed, bored and reamed, then turned true on the outside tread. They are next shrunk on accurately machined hubs-being hardened at the same time -hardened to resist battering blows just as are the heads of first-class forged hammers or sledges.

The rollers, complete, are mounted on anti-friction bearings to insure easy running, bearings with seals to retain lubricant and to prevent entrance of sand and ruinous grit.


The truck rollers of Best Tractors run over tracks which are true and straight. Tracks are made from drop forged hardened links which have been accurately machined top and bottom and large hardened spools and pins at each joint contribute to the long life which may be expected from the tracks on Best Tractors.

### E. F. CRAVEN

"The Road Machinery Man"


GREENSBORO, N. C. :-:

STATE DISTRIBUTOR




"When Greek meets Greek." Both the sledge and the flanged roller rims are hardened drop forged steel.





ONE OF THE NORTH CAROLINA STATE HIGHWAY DEPARTMENT'S NO. 12 ROAD KING CUTTING DOWN A ROUGH DITCH BANK

# in North Carolina



Adams Graders are built in 61/2 ft. to 12. ft. blade lengths. There is a size to suit your needs and power exactly.

DAMS Graders have proved their superiority and their ability to build the most miles of Good Roads per dollar or per day. There's only one reason—the Adjustable Leaning wheels are an exclusive feature on Adams Graders by means of which the weight of Adams Graders is leaned toward and balanced against the load. This overcomes side-draft and skidding, increases capacity and lessens the draft. This feature also enables Adams Graders to do difficult ditch and bank work, not successfully accomplished with other graders.

Every Adams Grader is guaranteed to prove these claims. Write today for catalog and let us show you how Adams Graders will reduce your grading

Write Our Local Distributor

J. C. BENJAMIN

733 WEST HARGETT STREET RALEIGH, NORTH CAROLINA

J. D. ADAMS & COMPANY

HOME OFFICE AND FACTORY: INDIANAPOLIS, INDIANA

# ADAMS ADJUSTABLE LEANING WHEEL GRADERS